



प.सं. - ०८२/८३

च.नं. - २०२६

माडी नगरपालिका नगर कार्यपालिकाको कार्यालय

वसन्तपुर, चितवन
बागमती प्रदेश, नेपाल



मिति-२०८२/११/२५

विषय: दरभाउ पेश गर्ने सम्बन्धमा ।

श्री सबै फर्म तथा कम्पनीहरु,

..... ।

प्रस्तुत बिषयमा यस नगरपालिकाको स्वीकृत बजेट अनुसार जिल्ला प्रशासन कार्यालय परिसरमा प्रतिक्षालय निर्माण कार्य गर्नुपर्ने भएकोले यस पत्रसाथ संलग्न बिल अफ क्वान्टिटी (BOQ) मा उल्लेखित कार्यहरु के-कति दरमा गर्न सकिन्छ? ईच्छुक फर्म तथा कम्पनीहरुले फर्म तथा कम्पनी दर्ता प्रमाणपत्र, आ.व.२०८२/८३ को लागि नवीकरण भएको निर्माण व्यवसायी इजाजत पत्र, प्यान/भ्याट दर्ता प्रमाणपत्र, आ.व.२०८१/८२ को कर चुक्ता प्रमाणपत्रको प्रतिलिपिहरु संगलन गरि मिति २०८२/१२/०१ गते भित्र यस कार्यालयमा दरभाउ पेश गर्नुहुन अनुरोध छ।


ज्योति प्रसाद भुसाल
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

Madi Municipality
Office of the Municipal Executive
Basantapur, Chitwan
Bagmati Province, Nepal

Project Name: Construction of Waiting Shed on District Administration office.
Address: Bharatpur, Chitwan



(Signature)
प्रमुख प्रशासकीय अधिकृत

Bill of Quantity(BoQ)

S.N.	Description	Unit	Quantity	In Figure		Amount	Remarks
1	Earthwork in excavation using manual means including lift up to 1.5m and disposal of soil up to a lead of 10m. as per drawing, specification and instruction of the engineer, all complete.	Cum	5.43				
2	Earthwork in Filling with compaction in 15cm all completeEarth Filling: Earth work in filling in foundation, floor etc. shall be done with good excavated soil in the floor with proper ramming in 20cm layers, after sprinkling water and consolidating to 15 cm layer, as per drawing, specification and instruction of the engineer, all complete.	Cum	9.92				
3	Providing and laying single layer of flat Stone soling	Cum	3.96				
4	Plain cement concrete of grade M15 (1:2:4) with cement sand crushed aggregate under wall, floor & column foundation etc. including protection of sides, laying compacting, curing with all complete.	Cum	2.95				
5	Providing and laying of brick masonry work in (1:6) cement, sand mortar upto ground floor with approved quality first class chimney made bricks in perfect line and level including wetting the bricks packing the joints and curing, with necessary scaffolding work, including supplying of all materials, labour, lead and lift. Work all complete as per design, drawing, specification and approval of Engineer.	Cum	4.11				
6	Salwood for beam, joist, post, Roofing etc. work as per as design.	Cum	1.49				
7	Providing and laying 12.5mm thick plaster upto required line and perfect smooth level in 1:4 cement sand mortar on wall surface including necessary scaffolding, cleaning & wetting the surface and proper curing for 15 days as per drawing, specification and instruction of engineer.	Sqm	8.05				
8	2 coats of ready made enamel paint of approved colour over 1 coat of primer.	Sqm	72.13				
9	Supply & fitting of 0.41mm CGI Roofing Sheet	Sqm	28.26				
10	25mm thick flag stone in cement sand mortar 1:4 ratio as per as direction.	Sqm	24.34				
11	supply & fitting of Khapada on Roofing as per as direction.	Sqm	28.26				
12	Sculpture & wall writing about madi municipality	Job	1.00				
13	Hoarding Board for Contract Information	Nos.	1.00				
			Total				
			VAT 13%				
			Grand Total				

Firm/Suppliers Name:
Address:
stamp:
Sign:
Date: